



NOTE:
 Where the edge of the patch or section of removed pavement is less than 10' from a transverse expansion or contraction joint or crack, the entire section of pavement shall be removed up to the joint or crack and replaced with new concrete and ABC stone in accordance with the most current N.C.D.O.T. Standard Specifications.

The backfill shall be made in 6" layers and shall be compacted to at least 95% of standard density (AASHTO Method T-99). Each layer must be thoroughly tamped by a mechanical tamp before the next layer is placed.



DATE 8/16/04	REVISED 2/19/19	SCALE NOT TO SCALE	DETAIL M-2
-----------------	--------------------	-----------------------	---------------

CONCRETE PAVEMENT REPAIR DETAIL
 CITY OF BURLINGTON, NORTH CAROLINA
 ENGINEERING DEPARTMENT